Name: Torrecampo, Juan Piolo S.	Date Performed: Nov 15, 2022
Course/Section: CPE 232 / CPE31S22	Date Submitted: Nov 18, 2022
Instructor: Dr. Jonathan Taylar	<b>Semester and SY:</b> 1st Sem, 2022 - 2023

**Activity 11: Containerization** 

#### 1. Objectives

Create a Dockerfile and form a workflow using Ansible as Infrastructure as Code (IaC) to enable Continuous Delivery process

#### 2. Discussion

Docker is an open platform for developing, shipping, and running applications. Docker enables you to separate your applications from your infrastructure so you can deliver software quickly. With Docker, you can manage your infrastructure in the same ways you manage your applications. By taking advantage of Docker's methodologies for shipping, testing, and deploying code quickly, you can significantly reduce the delay between writing code and running it in production.

Source: <a href="https://docs.docker.com/get-started/overview/">https://docs.docker.com/get-started/overview/</a>

You may also check the difference between containers and virtual machines. Click the link given below.

Source: https://docs.microsoft.com/en-us/virtualization/windowscontainers/about/containers-vs-vm

#### 3. Tasks

- 1. Create a new repository for this activity.
- 2. Install Docker and enable the docker socket.
- 3. Add to Docker group to your current user.
- 4. Create a Dockerfile to install web and DB server.
- 5. Install and build the Dockerfile using Ansible.
- 6. Add, commit and push it to your repository.

#### 4. Output

Instead of manually installing the docker in the server and configuring it for web server (LAMP Server) through Docker containerization, I have created a fully functional ansible playbook that installs docker and its dependencies, builds an image through Dockerfile and deploys that image.




Figure 1. The screenshot above shows the page of the newly created repository for this activity.

```
~/Desktop ) git clone git@github.com:piolotorrecampo/CPE232-Activity_11.git Cloning into 'CPE232-Activity_11'...
remote: Enumerating objects: 3, done.
remote: Counting objects: 100% (3/3), done.
remote: Total 3 (delta 0), reused 0 (delta 0), pack-reused 0
Receiving objects: 100% (3/3), done.
~/Desktop took 4s )
```

Figure 2. The image above shows the cloning of the repository in the local machine.

```
CPE232-Activity_11 on | main | mkdir ubuntu_docker

CPE232-Activity_11 on | main | mkdir ubuntu_docker/files ubuntu_docker/handlers ubuntu_docker/tasks ubuntu_docker/tests

CPE232-Activity_11 on | main | locker| | buntu_docker/files/Dockerfile

CPE232-Activity_11 on | main | locker| | buntu_docker/handlers/main.yml

CPE232-Activity_11 on | main | locker| | buntu_docker/tasks/install.yml ubuntu_docker/tasks/configure.yml ubuntu_docker/tasks/main.yml

CPE232-Activity_11 on | main | locker| | buntu_docker/tasks/install.yml ubuntu_docker/tasks/install.yml ubuntu_docker/tasks/main.yml
```

Figure 3. The sequence of commands above creates the structure of our ansible role to create a web server using docker.




Figure 4. The picture above shows the tree structure of the web server ansible role directory where Ubuntu is used as a host operating system.



Table 1. The table above shows the contents of Dockerfile in the "files" directory.

# File and its Contents under "handlers" Directory main.yml main.yml main.yml name: Start docker service: name: "{{ item }}" state: restarted enabled: true with\_items: - docker - containerd

Table 2. The table above shows the contents of main.yml in the "handlers" directory.



```
- name: Ensure group docker exists
                                 group:
                                  state: present
                              - name: Adding docker to the group of the current user
                                 append: yes
                                service:
  name: "{{ item }}"
  state: started
                                 dockercontainerd
                              - name: Install python sdk
[] become_user: "{{ ansible_env.SUDO_USER }}"
                                 - name: Verifying docker service
shell: systemctl list-unit-files | grep docker
                                 register: docker_service
                                 - debug:
   msg="{{ docker_service }}"
                                  shell: groups userver
register: user_groups
                                 - debug:
    msg="{{ user_groups }}"
                                   msg="{{ docker_installation }}"
configure.yml
                                                   🜣 configure.yml 🛛 🗙
                                                         path: /home/userver/docker_config
state: directory
                                                      - name: Copying the Dockerfile
                                                          dest: /home/userver/docker_config
owner: userver
group: userver
                                                      - name: Creating volume
                                                         path: /home/userver/pages
```

Table 3. The table above shows the contents of each file in the "tasks" directory namely main.yml install.yml and configure.yml.



#### inventory



Table 4. The table above shows the contents of each file in the "tests" directory namely test.yml, inventory and ansible.cfg.

```
PE232—Activity_11/ubuntu_docker/tests on | main [?] via 0 v3.10.8 +12 > ansible-playbook --ask-be
BECOME password:
changed: [192.168.30.135]
TASK [../../ubuntu_docker : Downloading docker components] ****************************
changed: [192.168.30.135] => (item=containerd.io_1.6.9-1_amd64.deb)
changed: [192.168.30.135] => (item=docker-ce-cli_20.10.21~3-0~ubuntu-jammy_amd64.deb)
changed: [192.168.30.135] => (item=docker-ce_20.10.21~3-0~ubuntu-jammy_amd64.deb)
changed: [192.168.30.135] => (item=docker-compose-plugin_2.6.0~ubuntu-jammy_amd64.deb)
changed: [192.168.30.135] => (item=docker-compose-plugin_2.6.0~ubuntu-jammy_amd64.deb)
TASK [../../ubuntu_docker : Adding docker to the group of the current user] ***********************************
changed: [192.168.30.135]
changed: [192.168.30.135]
```

```
"stdout_lines": [

"docker.service enabled enabled",
enabled enabled"
ok: [192.168.30.135] => {
"msg": {
 "stderr_lines": [],
```

Figure 5. The screenshot above shows the output after running the playbook. It also shows the verification for the user's groups, docker installation and container/s status using debug messages.

#### Summary of Debug Messages from the Output and Screenshot of its Equivalent in the Server

### Adding Docker to Group

The debug message shows the docker services by executing the command "systemctl list-unit-files".

userver@ubuntu–server:~\$ groups userver userver : userver adm cdrom sudo dip plugdev lxd docker

#### **Docker Service**

The debug message shows the docker services by executing the command "systemctl list-unit-files".

```
userver@ubuntu-server:~$ sudo systemctl list-unit-files | grep docker
docker-2c47792670fa9a5883a8915740e494fbf022896db53a036313cb56b1b69dfacc.scope transient -
docker.service enabled enable
docker.socket enabled enable
docker.socket
```

#### Verify Docker Installation

The debug message get the output of the command "docker –version" to verify that docker is installed successfully.

userver@ubuntu–server:~\$ docker ––version Docker version 20.10.21, build baeda1f

## Verify if the Container is Running

The debug message shows the running containers. It is achieved by running the command "dcoker ps".




Table 5. The table above shows the summary of debug messages with the screenshot of its equivalent in the server.

Figure 6. The image above shows the process of pushing the contents of the repository to Github.



Figure 7. The picture above shows the pages of the repository.

**Note:** Before proceeding in deploying the playbook, I have first installed the module for docker that helps to create, build and deploy containers. The command **[ansible-galaxy collection install community.docker]** is used to download the community.docker module. Also, there is another dependency named "Docker SDK" that should be installed on the server. The installation is already included in the playbook.

#### 5. Links

#### References:

- https://docs.ansible.com/ansible/latest/collections/community/docker/docker\_image\_module.html
- https://docs.ansible.com/ansible/2.9/modules/docker container module.html
- https://www.youtube.com/watch?v=CQk9AOPh5pw&t=600s
- https://docs.docker.com/engine/install/ubuntu/

Github Repository: <a href="https://github.com/piolotorrecampo/CPE232-Activity\_11.git">https://github.com/piolotorrecampo/CPE232-Activity\_11.git</a>

#### 6. Reflections:

Answer the following:

- 1. What are the benefits of implementing containerizations?
  - The benefits of implementing containerizations in a server is that it enables it to isolate applications in a lightweight virtual machine rather than providing a separate fully functional operating system. The operating system installed in a container is a portion of the full operating system which only uses the needed file systems to run. Since a container utilizes a smaller amount of memory, then we can deploy multiple containers that are running simultaneously. The other benefits of containerization is managing and building the containers by the use of Dockerfile. Dockerfile is a set of instructions that instructs the container to upgrade, install some applications and many more. We can visualize these instructions using a terminal but different in syntax. Containerization also implements persistent storage and provides an isolated view of virtual network adapters.

#### 7. Conclusions:

The activity achieved its objective to practice the student in creating a Dockerfile and using the ansible to build an image with it and deploy it as a container which enables the continuous delivery process for an enterprise. This activity gives me a clear understanding of how Docker works in a live environment. Docker reduces the resources in a computing system that enables it to replace a full working operating system to minimal installation by using docker containerization. Containerization works by isolating a group of applications in the host operating

system. It is not a fully operational operating system but it has the dependencies and is capable of launching an application.

In performing this activity, I have decided to make all of the steps regarding installation and enabling docker, building a Dockerfile, and deploying the container in one ansible playbook. In installing and enabling the services of docker, I relied on the steps in the official page of docker and convert into ansible syntax. In building the Dockerfile and deploying it as a container, I utilized the given code in the ansible official documentation for docker support. Overall, this activity gives me confidence in writing Dockerfile and as well as building an image and deploying a container.

#### 8. Honor Pledge:

"I affirm that I will not give or receive unauthorized help on this activity and that all will be my own."